

8-15-88

To: I 030968  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-21,230-0000  
NE SW NE, SEC. 28, T 32 S, R 37 (W)X  
3630 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5003  
Operator: McCoy Petroleum Corporation  
Name & Address: 110 South Main, Suite 500  
Wichita, KS 67202

Lease Name Hittle Well # 1-28  
County Stevens 211.25  
Well Total Depth 6500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1752

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor: Sweetman Drilling, Inc. License Number 5658

Address 110 South Main, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 2:50 a.m. Day: 15 Month: 8 Year: 19 88

Plugging proposal received from Eugene Salogo

(company name) Sweetman Drilling, Inc. (phone) 316-265-5561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3139' GL  
Anhydrite 1745-52'

1st plug at 3000' with 100 sx cement, 2nd plug at 1780' with 50 sx cement,

3rd plug at 870' with 25 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:50 a.m. Day: 15 Month: 8 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 1780' with 50 sx cement,

3rd plug at 870' with 25 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (check box) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 8-16-88

INV. NO. 21866