

To: 1 020846 3-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,109-0000
C SE SW, SEC. 34, T 32 S, R 37 W/E
660 feet from S section line
3300 feet from E section line
Lease Name Sharp Well # 1
County Stevens
Well Total Depth 6450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1736

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393
Operator: A.L. Abercrombie, Inc.
Name & Address Rt. 1, Box 56
Great Bend, KS 67530

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 17 Month: 3 Year: 19 95

Plugging proposal received from Manny Boatright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 6395', PBTD 6336', Perfs at 5974-6011'

1st plug sand back to 5925' and dump 5 sx cement on top of sand through barrier,

2nd plug shoot pipe and pump 140 sx cement at stub,

3rd plug pump 40 sx cement at 650',

4th plug pump 15 sx cement at 60-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:30 p.m. Day: 17 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 50' above perfs with 5 sx cement on top,

2nd plug shot pipe at 5000', 4000', 3600', could not pull. Shot at 2300' and pumped

140 sx cement at stub (estimate top of cement at 1650').

3rd plug pumped 40 sx cement at 650',

4th plug pumped 15 sx cement at 62-0'.

Mud between all plugs.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
(If billed) observe this plugging.

DATE 3-23-95

INV. NO. 42445

Signed Glenn Barlow
(TECHNICIAN)