

10-1315-129-00003-0000

1 020333

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA

NE NE SW, SEC. 5, T 32 S, R 43 W/E  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Dreyer Well # B-1

Operator: Coastal Oil & Gas Corporation  
Name & Address 211 N. Robinson, Suite 1700  
Oklahoma City, OK 73102

County Morton 115.53  
Well Total Depth 3555 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Dowell Schlumberger, Inc. License Number \_\_\_\_\_

Address P.O. Box 887, Ulysses, KS 67880

Company to plug at: Hour: 10:15 a.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from Robert Martin

(company name) Coastal Oil & Gas Corporation (phone) 316-697-2137

were: 5 1/2" at 3476' w/200 sx cement, PBTD 3268', Perfs at 2966-3244'

1st plug pump 5 sx hulls and 262 sx cement down 5 1/2", 2nd plug pump 68 sx cement down annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 13 Month: 10 Year: 19 90  
10/10:

ACTUAL PLUGGING REPORT 1st plug pumped 5 sx hulls & 262 sx 60/40 Pozmix & 150 sx common cement down 5 1/2", 2nd plug pumped 50 sx cement down 8 5/8" annulus. Cement dropped. 10/13: Tagged top of cement at 1120', swabbed down 1100', 3rd plug pumped 101 sx RFC-2 with 2% cc & 1/4# celloflakes down 5 1/2". Pressured to 720#.

4th plug pumped 22 sx same cement down 8 5/8". Pressured to 670#.

Both full when capped.

Remarks: Cemented by Dowell Schlumberger, Inc. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-22-90

INV. NO. 29688

RECEIVED STATE CORPORATION COMMISSION  
OCT 17 1990 Signed Steve R. Barlow (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

10-17-90

FORM CP-2/3  
Rev. 01-84