

1 060868

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6378

Operator: Hawkins Oil and Gas, Inc.
Name & Address: P.O. Box 1282
Liberal, Kansas 67901

API NUMBER 15- 129-20,820-0000

C SW SW 8, SEC. 8, T 32 S, R 43 W/E
330 feet from S section line
4950 feet from E section line

Lease Name Acree Well # 1-8

County Morton 178.95

Well Total Depth 5506' feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1612'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sage Drilling Co. License Number 5421

Address 202 S. St. Francis, Wichita, KS 67202

Company to plug at: Hour: 5:15 pm Day: 22 Month: 7 Year: 1986

Plugging proposal received from Tommye Diseker

(company name) Hawkins Oil & Gas, Inc. (phone) 316-624-8327

Elevation 3649 GL

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3400' with 40 sx cement

2nd plug at 2850' with 40 sx cement

3rd plug at 30' outbase surface pipe with 50 sx cement

4th plug at 600' with 30 sx cement

5th plug 40' to 0' with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement,

7th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 22 Month: 7 Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 3600' with 40 sx cement, 2nd plug at 2850' with
40 sx cement, 3rd plug at 1562' with 50 sx cement, 4th plug at 600' with 30 sx cement,
5th plug at 40' to 0' with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement,
7th plug to circulate mouse hole with 10 sx cement.

Remarks: Dowell pumped class H cement

(If additional description is necessary, use BACK of this form.)

INVOICED

(xxx) do not observe this plugging.

DATE 8-20-86

INV. NO. 14776

AUG 20 1986

Signed Paul A. Luthi
(TECHNICIAN)

8-20-86