

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-10037-00-00  
Spot: CNENESW Sec/Twnshp/Rge: 16-32S-43W  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease/Unit Name: DREYER Well Number: 1-16  
County: MORTON Total Vertical Depth: 3390 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN, LLC  
Address: 3200 FIRST PLACE TOWER  
TULSA, OK 74103

Conductor Pipe: Size feet: 8/10.18  
Surface Casing: Size 8.625 feet: 611 WITH 300 SX CMT  
Production: Size 5.5 feet: 3388 WITH 300 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/22/2002 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2900' WITH 2 SX CMT. 1ST PLUG AT 1600' WITH 50 SX CMT. 2ND PLUG AT 640' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/23/2002 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

CIBP @ 3180'. PERFS AT 2953-3292 (339 PERFS). SET CIBP @ 2900' WITH 2 SX CMT. LOADED HOLE & PRESSURED TO 500 PSIG. HELD GOOD. 1ST PLUG SHOT 5 1/2" OFF AT 1420'. COULDN'T PULL PIPE. SHOT PIPE OFF AT 1020', PULLED SHORT JOINT, PUMPED 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 640' & PUMPED 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH PIPE TO 40'. SDON. 08/23/02: 4TH PLUG AT 40' WITH 10 SX CMT.

RECEIVED

SEP 19 2002

KCC WICHITA

9-19-02

Remarks: USED COMMON CEMENY BY SARGENTS. RECOVERED 1030' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED

SEP 03 2002

DATE

9-19-02

INV. NO.

2003060537

Form CP 2/3