

1 110098

15-119-10235-0000  
2-19-88

156  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-4924

C NE NE, SEC. 3, T 34 S, R. 30 W/E

660 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Novinger Unit Well # 1001 W

Operator: Cities Service Oil & Gas Corp.  
Name &

County Meade 174.85

Address 3545 N.W. 58th Street

Well Total Depth 5380 feet

Oklahoma City, OK 73112

Conductor Pipe: Size 13 3/8 feet 723

Surface Casing: Size 9 5/8 feet 2707

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 18 Month: 2 Year: 19 88

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 816-624-7455

were: 5 1/2" at 5380' PBD 5347' Perfs at 5290-96'

1st plug set CIBP at 5000' with 2 sx cement on top,

2nd plug pump 50 sx cement on stub,

3rd plug pump 50 sx cement at 2730',

4th plug pump 50 sx cement at 750', 5th plug pump 15 sx cement at 40-0'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 19 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5100' with 2 sx cement on top of bridge plug,

2nd plug pumped 50 sx cement at 2740',

3rd plug pump 50 sx cement at 750',

4th plug pump 20 sx cement at 40-0'.

Mud between plugs.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used Class H cement by Sargent's. Recovered 2810' of 5 1/2" casing & 1217' of 9 5/8".

(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 2-29-88

Signed James R. Kary (TECHNICIAN)

INV. NO. 19949

2-19 MAR 24 1988

FORM CP-2/3  
Rev. 01-84