

1090912

TO:

4-5

API NUMBER 15- 119-20,992 - 0000

STATE CORPORATION COMMISSION

C NW NE SE, SEC. 03, T 34 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DeMOSS 3 WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE 198.25

OPERATOR LICENSE # 5278

WELL TOTAL DEPTH 6100 FEET

OPERATOR: ENRON OIL & GAS

PRODUCTION CSG: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

NAME AND 20 N. 3  
20N. BROADWAY, SUITE 800

SURFACE CSG 8 5/8" FEET 1536'

ADDRESS OKLAHOMA CITY, OK 73102

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A X

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ABERCOMBIE DRILLING LICENSE NUMBER 30684

ADDRESS 150 N. MAIN, STE 801 WICHITA, KS 67202-1383

COMPANY TO PLUG AT: HOUR: 3:PM DAY: 5 MONTH: 4 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM BILL CRAIG

(COMPANY NAME) ABERCROMBIE DRILLING (PHONE) 316-262-1841

WERE: 1-100 SX AT 3450, 2-50SX AT 1550, 3-50 SX AT 700, 4 10SX AT 40

15 SX RAT HOLE 10SX IN MOUSE HOLE 60/40 6%GEL 1/4 FLO SEAL

PLUGGING PROPSAL RECEIVED BY: STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: 9:30 PM DAY: 5 MONTH: 4 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILLPIPE

1ST PLUG 100 SX AT 3450' 2ND PLUG 50 SX AT 1550' 3RD PLUG 50 SX 700

4TH PLUG 10 SX 60' 5TH PLUG 15SX RAT HOLE 10 SX MOUSE HOLE

REMARKS: USED 60/40 POZ 6% GEL 1/4 LB FLO SEAL BY HALLIBURTON

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK

OF THIS FORM.)

I (DID)NOT OBSERVE THIS PLUGGING.

SIGNED \_\_\_\_\_  
(TECHNICIAN)

FORM CP-2/3

APR 15 1998

CONSERVATION DIVISION  
Wichita, Kansas

4-8-98

**INVOICED**

DATE APR 15 1998

INV. NO. 50353

4-5