

2050185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-191-20,546-0000

NW/4 SEC. 7, T 33 S, R 1 W 14

660 feet from N section line

660 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License 5469

Lease Name Covelson #1 Well # 1

Operator: Anadarko Prod. Co.

County Sumner

Name & Address Box 351

Well Total Depth 4315 140.24 feet

Liberal, Ks. 67901

Conductor Pipe: Size - feet -

Surface Casing: Size 8 7/8 feet 286

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor M & B well service License Number 6055

Address Wellington Ks.

Company to plug at: Hour: 1:30 Day: 18 Month: Oct Year: 1984

Plugging proposal received from Rich Coumel

(company name) M & B well service (phone)

were: sand off bottom & dump 4 ex cement. Circulate
Cement from 300 ft. to surface inside & outside of
4 1/2"

STATE CORP. COMMISSION

10-24-84 OCT 24 1984

CONSERVATION DIVISION

WICHITA, KANSAS

Plugging Proposal Received by Glenn L. Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 PM Day: 18 Month: Oct Year: 1984

ACTUAL PLUGGING REPORT 4 1/2" casing set @ 4308, Perf. @ 4243-45 ft,
sand back to 4200' ft. & Dump 4 ex. Cement.

Run 1" pipe down outside of 4 1/2" casing to 352' & Circulate
Cement to surface. pull 1" pipe & Run down inside 4 1/2"
casing to 315 ft. & Circulate Cement to surface. pull 1"
Pipe

Remarks: Howee

INVOICED

if additional description is necessary, use BACK of this form.)

DATE 10-21-84 (did/did not) observe this plugging.

INV. NO. 4490

Signed Glenn L. Ward
(TECHNICIAN)

10-18

NOV 19 1984

RO