

To: 1 100103 3-6
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-129-00105-0000
API NUMBER-15- Completed 1954

SE SE NW, SEC. 22, T 32 S, R 43 WXX
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6593
Operator: Coastal Oil & Gas Corp.
Name:
Address: Nine Greenway Plaza, Ste. 2751
Houston, TX 77046

Lease Name Saunders Well #1-22
County Morton 110.66
Well Total Depth 3405 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 609

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number
Address

Company to plug at: Hour: 9 a.m. Day: 5 Month: 3 Year: 19 97

Plugging proposal received from Jayne Leuterman
(company name) Coastal (phone) 713-877-7654

Well squeezed 2/94 from
were: 5 1/2" at 3370' w/155 sx cement, CIBP 3200', Perfs at 2798-3294', 666-0' w/210 sx cement
1st plug spot 50 sx cement and 300 lbs. hulls to 2970',

2nd plug pump 55 sx cement down 5 1/2" from 670'-0',

3rd plug pump 75 sx cement down 8 5/8" X 5 1/2" annulus. 3-12-97

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 5 p.m. Day: 6 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pump 50 sx cement with 300 lbs. hulls, displaced to 2900'.
Let set overnight. 3/5/97

3/6/97 2nd plug tagged cement at 2900', pump another 50 sx cement. Let set 4 hours. Circulated
hole with mud.

3rd plug pulled tubing to 668' and pumped 60 sx cement, circulating cement to surface. Pulled
tubing. Topped off to surface. Cement did not fall.

Remarks: Used 60/40 Pozmix 3% cc by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 12 1997

INV. NO. 47739
3-6

Signed Jay Leuterman
(TECHNICIAN)