

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10154-00-00
Spot: CNW Sec/Twnshp/Rge: 10-32S-42W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease/Unit Name: HINES Well Number: 1
County: MORTON Total Vertical Depth: 3260 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: 201 E. RANDOLPH
HOWARD, KS 67349

Conductor Pipe: Size feet: 8/05.95
Surface Casing: Size 8.625 feet: 686 WITH 400 SX CMT
Production: Size 5.5 feet: 3260 WITH 160 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/26/2002 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT FOR BOTTOM PLUG. LOAD HOLE WITH MUD. 1ST PLUG AT 1100' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/28/2002 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3221'. PERFS AT 2802-3221. BP @ 3221'. PERFS AT 3242-47'. ON 03/26/02: PUMP 400# HULLS WITH 25 SX CMT THROUGH TUBING FOR BOTTOM PLUG. TOC @ 2600'. ON 03/28/02: TUBING STUCK IN HOLE. SHOOT OFF AT 2430'. PULL OUT OF HOLE. LOAD HOLE & SHOOT CASING OFF AT 1110'. 1ST PLUG PULL OUT OF HOLE. RUN IN HOLE WITH TUBING TO 1100'. LOAD HOLE. PUMP 50 SX CMT. GOOD CIRUCLATION. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 700'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

APR - 9 2002

CONSERVATION DIVISION

4-9-02

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1110' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland DIRTIP
(TECHNICIAN)
APR 04 2002

INVOICED

DATE

4-10-02

NV. NO.

2002061637

Form 21