

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10554-0000

API NUMBER NA

LEASE NAME RILEY

WELL NUMBER 4-27

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 27 TWP. 34S RGE. 42 ~~W~~ (W)

COUNTY Morton

Date Well Completed 7/56

Plugging Commenced 12/19/89

Plugging Completed 12/29/89

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/19/89 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No, Well Record & logs already on file.

Producing Formation Morrow Depth to Top 4564 Bottom 4576 T.D. 4590

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil	4564	4576	5 1/2	4624	2431

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- 1.) Displaced hole w/100 bbl mud via 2 3/8 tbg
- 2.) Spotted 30 sxs common cmt from 4540-4340
- 3.) Shot off casing @ 2431
- 4.) Spotted 30 sxs from 2400-2300
- 5.) Spotted 50 sxs common from 1598-1398
- 6.) Spotted 35 sxs common from 700-600
- 7.) Spotted 10 sxs common from 40-0
- 8.) Rec 2431' 5 1/2", 15.5# csg
- 9.) Cut off wellhead 3' below GL & capped well

(If additional description is necessary, use BACK of this form.)

(over)

Name of Plugging Contractor Sargent's Casing Pullers Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.


M. L. Pease - Division Production Manager (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) M. L. Pease - Division Production Mgr. P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 26 day of January, 19 90

My Commission Expires:



Notary Public

10.) Restore location 11.) Witnessed by Glenn Barlow with the Kansas Corporation Commission.

