


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

C  
O  
P  
Y

WELL PLUGGING RECORD



C Morton County. Sec. 27 Twp. 34 Rge. 42 ~~W~~ (W)  
T Location as "NE/CNW&SW" or footage from lines 1650/f N Line, 990/f E Line  
E Lease Owner Cities Service Oil Company  
D Lease Name Hamilton "B" Well No. 2  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-17-56 19  
Application for plugging filed 8-24-56 19  
Application for plugging approved 8-25-56 19  
Plugging commenced 9-27-56 19  
Plugging completed 10-3-56 19  
Reason for abandonment of well or producing formation Unable to shut off salt water.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Phillippe  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4700 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas & Water	4560	4568	8-5/8"	1363	None
Cherokee	Water	3968	3974	5 1/2"	4699	2107
"	Water	3938	3948			
Marmaton	Water	3780	3788			
Marmaton	Water	3694	3704			
Lower L-K.C.	Water	3496	3506			
Lower Lan. K.C.	Water	3380	3390			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped plug to 2580'; squeezed 100 sacks of cement to 2000#; pulled 2107' of 5 1/2" casing; filled hole with heavy rotary mud to 20' of surface, cement to 4' below ground level at which point the 8-5/8" casing was cut off and a steel cap welded on.

RECEIVED  
11-6-56  
NOV - 5 1956  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Lease & Well Servicing  
Address 1700 S. Main St., Borger, Texas

STATE OF KANSAS COUNTY OF SEWARD, ss.  
H. V. Anderson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. V. Anderson H. V. Anderson  
Box 70, Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of October, 1956

J. T. Mabrey J. T. Mabrey  
Notary Public.

PLUGGING  
FILE SEC 27 T. 34 R. 42 W  
BOOK PAGE 93 LINE 2