


15-151-00300-50-02

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pratt County, Sec. 28 Twp. 28 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner Bennett & Roberts Oil Operations
Lease Name Petrie Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 1/1 19 54
Application for plugging filed 5/10 19 54
Application for plugging approved 5/11 19 54
Plugging commenced 5/12 19 54
Plugging completed 5/17 19 54
Reason for abandonment of well or producing formation Not enough oil to produce economically
If a producing well is abandoned, date of last production 4/28 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 4602 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	392'	None
				5 1/2	4583	3813

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 4445' dumped 5 sax cement with dump bailer, top of cement 4410'. Pumped in 25 sax mud at 1800' through 5 1/2" casing by Sun Cementing Co. Set rock bridge at 300'. Dumped 20 sax cement, top of cement 240'. Filled with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J & M Casing Pulling Co.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of May, 19 54

My commission expires 6/17/54

Clara Sumner
Notary Public.

PLUGGING
FILE SEC 28 T 28 R 12W
BOOK PAGE 33 LINE 25

RECEIVED
MAY 20 1954
5-20-54
CONSERVATION DIVISION
Wichita, Kansas

Bennett & Roberts Oil Operations
Petrie #1

SE SE NE 28-28-12
Pratt County, Ks.

Comm: 12/3/53
Comp: 1/1/54

R.T.D. 4602

Casing
8 5/8 @ 392
5 1/2 @ 4583

Cement
200 sx
100 sx

Tops:

Cimerron Anhyd.	1270- 618
Heebner Shale	3547-1659
Douglas Sand	3613-1725
Brown Lime	3742-1854
Lansing Lime	3758-1870
Mississippian Lime	4192-2304
Mississippian Chert	4204-2316
Kinderhook Shale	4281-2393
Viola Lime	4343-2455
Simpson Shale	4451-2563
Simpson Dolo.	4456-2568
Simpson Sand	4473-2585
Arbuckle Dolo.	4561-2673

<u>Formation:</u>	<u>Depth:</u>
Shale	150
Sand	235
Shale & Shells	350
Red Bed	790
Gray Shale	950
Shale & Shells	1270
Anhydrite	1295
Shale & Shells	1540
Shale	1750
Lime & Shale	1855
Lime	2135
Lime & Shale	2935
Lime	3025
Lime & Shale	3272
Sandy Lime	3460
Lime & Shale	3692
Lime	4200
Chert	4215
Lime	4240
Lime & Stks Chert	4283
Lime & Shale	4334
Lime & Stks Chert	4374
Cherty Lime	4403
Viola	4447
Sand	4496
Simpson	4522
Shale	4556
Shale & Sand	4564
Arbuckle	4602

STATE OF KANSAS
COUNTY OF RUSSELL

I do hereby certify that the above information is true and correct
to the best of my knowledge.

Jim Gale

Subscribed and sworn to before me this 24th day of December, 1953

Charles L. Lamm
Notary Public

My commission expires 6/17/54

