

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 28 Twp. 28 Rge. 12 ~~00X~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner Prime Drilling Company

Lease Name Petrie Well No. 1

Office Address 814 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 18 19 59

Application for plugging filed November 18 19 59

Application for plugging approved November 18 19 59

Plugging commenced November 18 19 59

Plugging completed November 18 19 59

Reason for abandonment of well or producing formation no oil or gas found
in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp, Stafford, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4486' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	279'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 260'. Set Plug #1 at 260' with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' cemented with 10 sacks cement.

Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
12-9-59
DEC 9 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company

Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.

R. R. McNicol (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R.R. McNicol

814 Union Center, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of November, 19 59

My commission expires Sept. 30, 1963

Darlene May Notary Public



ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company
and Benedict Oil Associates
PETRIE NO. 1
NW NW NE Section 28-28S-12W,
Pratt County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 10-31-59
COMP: 11-18-59

Remarks: Set 8-5/8" surface casing
at 279' cemented with
200 sacks HA-500 Pozmix.

Formations:

Shale & Sand	135'
Sand	250'
Red Bed	279'
Red Bed & Shells	498'
Red Bed	955'
Red Bed Shale	1310'
Shale & Shells	1710'
Shale & Lime	1865'
Lime	2400'
Lime & Shale	2615'
Shale & Lime	2880'
Lime	2920'
Lime & Shale	3020'
Shale & Lime	3130'
Lime & Shale	3245'
Shale & Lime	3295'
Lime	3470'
Lime & Shale	3705'
Lime	4205'
Chert	4216'
Lime	4463'
Lime & Sand	4470'
Lime	4480'
Sand	4486'
Rotary Total Depth (D&A)	4486'

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1959
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol