


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pratt County. Sec. 28 Twp. 28 Rge. 12 SESSS (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines NW NW NW
Lease Owner K & E Drilling, Inc. - Bell Oil and Gas Co.
Lease Name Dietz Well No. 1
Office Address 1006 Central Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed June 12, 1956 19
Application for plugging filed June 12, 1956 19
Application for plugging approved June 12, 1956 19
Plugging commenced June 12, 1956 19
Plugging completed _____ 19
Reason for abandonment of well or producing formation
commercial quantities of oil not found
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M/ A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	355'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 4614 to 300'. Set wooden plug with 20 sacks cement. Second plug at 40' and capped with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor 1006 K & E DRILLING, INC.
Address Central Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dale Silcott (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Dale Silcott
1006 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of June, 19 56

My commission expires June 25, 1956

James Maden
RECEIVED
STATE CORPORATION COMMISSION
6-20-56
CONSERVATION DIVISION
Kansas
Notary Public.

PLUGGING
FILE SEC. 28 T. 28 R. 12W
BOOK PAGE 71 LINE 30

BELL OIL AND GAS CO. - K & E DRILLING, INC.
Dietz #1

NW NW NW Sec. 28-28S-12W
Pratt County, Kansas

Comm: 5-26-56
Comp: 6-12-56
Total Depth: 4614

Casing

Cement

8 5/8" Set @ 355

225 sacks

FORMATION

DEPTH

Clay	0 - 30
Shale	30 - 65
Sand	65 - 260
Red shale	260 - 355
Sand	355 - 380
Red shale	380 - 695
Red Bed	695 - 895
Anhydrite	895 - 925
Shale & shells	925 - 1255
Shale & lime & shells	1255 - 1770
Lime	1770 - 2020
Lime & shale	2020 - 2875
Lime	2875 - 3000
Lime & shale	3000 - 3220
Lime	3220 - 3600
Shale & Lime	3600 - 3705
Douglas shale	3705 - 3757
B. Lime	3757 - 3771
Lansing - Kansas City	3771 - 3780
Lime	3780 - 4045
Lime - hard	4045 - 4080
Lime	4080 - 4160
Pump	4160 - 4210
Miss.	4210 - 4220
Lime (cherty)	4220 - 4258
Lime	4258 - 4285
Lime & shale	4285 - 4325
Shale & lime	4325 - 4380
Viola lime	4380 - 4385
Viola Lime	4385 - 4395
Lime	4395 - 4400
Viola	4400 - 4459
Lime	4459 - 4480
Simpson	4480 - 4547
Simpson shale	4547 - 4586
Arbuckle	4586 - 4614

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 19th day of June, 1956.

Frances Marler, Notary Public

My commission expires June 25, 1956

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC: 28 T 28 R 12W
BOOK PAGE: 71 LINE 30