

15151-00264-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Pratt

County. Sec. 6 Twp. 6 Rge. 28 (E) 14W(W)

Location as "NE/CNW/SW" or footage from lines NE NW NW  
Lease Owner Tomlinson-Kathol, Inc.  
Lease Name Moore Well No. 1  
Office Address 414 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9/29 19 59  
Application for plugging filed 9/29/ 19 59  
Application for plugging approved 9/29/ 19 59  
Plugging commenced 1 A.M. 9/29 19 59  
Plugging completed 4:15 A.M. 9/29 19 59  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well LaCamp - Stafford  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4745 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	400	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud 1st plug @ 350' w/20 sacks  
2nd plug @ 35' w/10 sacks

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Tomlinson-Kathol, Inc.  
Address 414 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gerald J. Kathol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald J. Kathol  
414 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of September, 19 59  
Esther Lamon  
Notary Public.

My commission expires Jan. 19, 1961

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1959  
10-3-59  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG  
 TOMLINSON-KATHOL, INC.  
 # 1 MOORE  
 NE NW NW, SEC. 6-28S-14W  
 PRATT COUNTY, KANSAS


Contractor - Tomlinson-Kathol, Inc.

Commenced: 9/14/59  
 Completed: 9/29/59  
 Elevation: 2022 RB

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	40	Clay	
40	190	Sand	
190	310	Clay	400' 8-5/8" w/350 Sks Cement
310	820	Shale	
820	1136	Red Bed & Sand streaks	
1136	1912	Shale	
1912	2084	Shale & Lime Streaks	
2084	2209	Shale & Lime	
2209	2235	Lime	
2235	2265	Sand	
2265	2300	Lime	
2300	2328	Sand	
2328	3032	Shale & Lime	
3032	3200	Shale	
3200	3565	Shale & Lime	
3565	3770	Lime	
3770	3981	Shale	
3981	4049	Shale & Lime	
4049	4115	Lime	
4115	4302	Lime	
4302	4379	Lime & Shale	
4379	4430	Lime	Heebner 3798
4430	4483	Shale & Sand	Toronto 3827
4483	4512	Shale & Lime	Douglas 3858
4512	4555	Lime & Shale	Brown Lime 3952
4555	4606	Chert	Lansing 3978
4606	4627	Chert	Cherokee 4426
4627	4646	Chert & Shale	Miss. Chert 4469
4646	4680	Lime - Shale	Viola 4535
4680	4721	Shale & Lime	Simpson 4617
4721	4741	Arbuckle	Arbuckle 4715
4741	4745	Arbuckle - RTD	RTD 4745

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 3 1959  
 CONSERVATION DIVISION  
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

  
 Gerald J. Kathol

State of Kansas )  
 )  
 County of Sedgwick )

Subscribed and sworn to before me this 2nd of October, 1959.

  
 Notary Public

My Commission Expires Jan. 19, 1961