

ATE OF KANSAS
ATE CORPORATION COMMISSION
D. S. Market, Room 2078
chita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-151-21,530-44-41

LEASE NAME Schoonover

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E. Section Line

SEC. 6 TWP. 28S RGE. 14W (E) or (W)

COUNTY Pratt

Date Well Completed

Plugging Commenced 12-18-97

Plugging Completed 2-24-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Case Production Company

DRESS Rt. 4 Box 131 McKinney, TX. 75050

PHONE# (972) 562-0735 OPERATORS LICENSE NO. 31953

Character of Well Oil

Oil, Gas, O&A, SWD, Input, Water Supply Well

The plugging proposal was approved on (date)

Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4749'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	429'	None
				4-1/2"	4716'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 4400' and 4 sacks cement. Shot pipe @ 3300', 2600', 2300', layed down 4-1/2" casing. Pumped 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, 8-5/8" plug and 100 sks. cement. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of March, 1998

RECEIVED
KANSAS CORP. COMM.

My Commission Expires:



Notary Public

Form CP
Revised 05-