

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas


WELL PLUGGING RECORD

PRATT

County, Sec. 20 Twp. 28S Rge. 14 (NW) W (W)

Location as "NE/CNW/SW" or footage from lines NW, NW, NE  
Lease Owner ROCK ISLAND OIL & REFINING COMPANY, INC.  
Lease Name MICHAEL Well No. 1  
Office Address 321 WEST DOUGLAS, WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed June 17, 1962  
Application for plugging filed June 17, 1962  
Application for plugging approved June 17, 1962  
Plugging commenced June 17, 1962  
Plugging completed June 17, 1962  
Reason for abandonment of well or producing formation No productible zone.

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4755 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	332'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits forming heavy mud, filled hole with heavy mud up to 300', pushed wooden plug to 300', capped with 30 sacks of cement through drill pipe.  
Filled hole up to 40' with heavy mud, pushed wooden plug to 40', filled hole up to base of well cellar with 15 sx. cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1962

7-13-62  
CONSERVATION DIVISION  
WICHITA, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Route #2, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Verne A. Morris (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris  
Route #2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 1962

My commission expires November 12, 1962

Grandenburg  
Notary Public

# WELL LOG

COMPANY **ROCK ISLAND OIL & REFINING COMPANY, INC.**

SEC. **20** T. **28S** R. **14W**

FARM **MICHAEL**

NO. **1**

LOC. **NW, NW, NE**


TOTAL DEPTH **4755'**

COUNTY **PRATT CO., KANSAS**

COMM. **May 28, 1962**

COMP. **June 17, 1962**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **10-3/4" @ 332' w/300 sax.**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

100	Surface clay
225	Sand
805	Red bed
830	Anhydrite
1380	Shale
1957	Shale & lime
2585	Lime
2980	Lime & shale
3150	Shale
3566	Lime & shale
3800	Lime
4075	Lime & shale
4419	Lime
4465	Cherty lime
4468	Lime, chert & sand
4501	Lime, shale, sand & chert
4513	Lime & chert
4550	Lime, chert & sand
4595	Chert
4624	Chert & lime
4633	Sand
4680	Shale
4699	Shale & lime
4703	Lime
4755	Lime & shale
4755	T. D.

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUL 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS }  
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 MICHAEL well.

Subscribed and sworn to before me this 29th day of June 1962

My Commission Expires November 12, 1962

*Verne A. Morris*  
\_\_\_\_\_  
NOTARY PUBLIC