


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 15 Twp. 28S Rge. 14 X(XX) (W)
Location as "NE/CNW%SW%" or footage from lines C-NE-NW-SE
Lease Owner Three G Oil, Inc. NW NE
Lease Name Woolfolk Well No. 1
Office Address 1101 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-17 1966
Application for plugging filed 8-17 1966
Application for plugging approved 8-17 1966
Plugging commenced 8-17 1966
Plugging completed 8-17 1966
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,609 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	383'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,609 feet rotary total depth to 320 feet. Set bottom plug at 320 feet and cemented with 1/2 sack hulls and 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40 feet and cemented with 1/2 sack hulls and 20 sacks cement, filling hole to bottom of cellar - 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966
8-22-66
CONSULTATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Merle Britting (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1966

My commission expires December 27, 1967.

Maxine Lampe
Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY Three G Oil, Inc.
 FARM Woolfolk No. 1

SEC. 15 T. 28S R. 14W
 LOC. C NE NW SE

TOTAL DEPTH 4,609'
 COMM. 8-2-66 COMP. 8-17-66
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Pratt

KANSAS



CASING

20 10
 15 8 5/8" 383' cem w/250 sx
 12 6
 13 5

1990 GR
 ELEVATION 1992 DF
 1995 KB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock 50
 Sand, red bed & shale 350
 Shale 383
 Red Bed 825
 Anhydrite 848
 Shale & Shells 1480
 Shell & Shale 1750
 Chert & Hard Sand 1755
 Shale & Sand 1825
 Lime & Shale 2043
 Shale & Lime 2390
 Lime 2495
 Lime & Shale 2835
 Shale & Lime 2975
 Lime & Shale 3216
 Shale & Lime 3430
 Lime & Shale 3720
 Shale & Lime 3880
 Lime & Shale 3963
 Lime 4076
 Lime & Shale 4093
 Lime 4256
 Lime & Chert 4324
 Lime 4347
 Lime & Chert 4386
 Lime 4408
 Mississippi 4454
 Lime 4490
 Lime & Shale 4531
 Simpson 4548
 Lime 4609
 Rotary T. D. 4609

Electric Log Tops

Anhydrite top	820	+1175
Anhydrite base	843	+1152
Topeka	3138	-1143
Heebner	3750	-1755
Toronto	3772	-1777
Douglas	3800	-1805
Br. Lime	3907	-1912
Lansing	3924	-1929
Base K. C.	4264	-2269
Conglomerate	4346	-2351
Mississippi	4390	-2395
Viola	4418	-2423
Simpson Shale	4462	-2467
Arbuckle	4544	-2549
Log T. D.	4609	-2614

RECEIVED
 STATE CORPORATION COMMISSION

AUG 22 1966

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Merle Britting
 Merle Britting

STATE OF KANSAS }
 SEDGWICK COUNTY } SS:

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 19th day of August, 1966.

Maxine Lampe
 Maxine Lampe, Notary Public

My Commission Expires:
 December 27, 1967.