

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-095-30001-00-00
API NUMBER

LEASE NAME Delp

WELL NUMBER #1

SPOT LOCATION NW-NW-SE

SEC. 18 TWP. 28 RGE. 5 (E) or (W)

COUNTY Kingman

Date Well Completed 11-24-64

Plugging Commenced 2/14/85

Plugging Completed 2/26/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D. R. Lauck Oil Co., Inc.

ADDRESS 221 S. Broadway, Suite 400 Wichita, Ks. 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? If not, is well log attached?

Producing formation KC Depth to top 3378 bottom 3408 T.D. 3900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	215	None
				5-1/2"	3892	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3325' & 5 sacks cement. Shot pipe at 3300', 3100', & 3000'
Pulled 93 joints of pipe. Plugged well with 3 hulls, 15 gel, & 100 sacks 60/40 poz.
2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 683
Address PO Box 176 Chase, Ks. 67524

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or MAR 05 1985
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and CONSERVATION DIVISION
the log of the above-described well as filed that the same are true and Wichita, Kansas
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 4th day of March, 1985



My Commission expires:

Irene Hoover
Notary Public

15-095-30001-00-00

D. R. Lauck Oil Company, Inc.
301 S. Broadway
Wichita, Kansas 67202

Delp #1
NW NW SE Sec. 18-28S-5W
Kingman County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.

Commenced: October 19, 1964

Completed: October 30, 1964

Drillers Log

Shale	60
Shale & Shells	775
Shells & Shale	1000
Lime & Shells	1080
Shale & Lime	1350
Lime & Shale	1520
Shale & Lime	2145
Shale	2383
Shale & Lime	2663
Lime & Shale	2831
Shale & Lime	3075
Lime & Shale	3147
Lime	3196
Shale & Lime	3244
Lime & Shale	3318
Lime	3494
Shale & Lime	3623
Lime & Shale	3708
Shale & Lime	3800
Lime & Chert	3822
Lime & Shale	3844
Lime	3900 RTD

Casing: 212' 8-5/8" Cemented with 175 sacks Cement, 3 sacks Calcium Chloride.
3892' 5-1/2" Cemented with 50 sacks Common Cement,
500 gallons Latex Cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1984

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1984

CONSERVATION DIVISION
Wichita, Kansas