


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ford County, Sec. 7 Twp. 29 Rge. 21 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines 0 W/2 NE/4  
Lease Owner Time Petroleum Company  
Lease Name Jay Balinger Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7-19-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7-21-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5111 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	272'	None
				4-1/2"	5109'	2996'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug of 50 sacks of cement had been previously set.  
Pulled 4 1/2" casing to 700' and pumped in 25 sacks of cement.  
Pulled 4 1/2" casing to 300' and pumped in 25 sacks of cement.  
Pulled balance of 4 1/2" casing and capped well with 15 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1965

CONSERVATION DIVISION  
Wichita, Kansas

7-29-65

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of July, 1965

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

DRILLERS LOG

42 Jay-Bolinger

CASING RECORD:  
Ran 264' of used  
8-5/8" casing.

COMPANY: Time Petroleum Company

DESCRIPTION: C W/2 NE  
Section 7-29-21W  
Ford County, Kansas

TOTAL DEPTH:  
5111'

COMMENCED: November 18, 1964

ELEVATION: 2408' KB

COMPLETED: December 2, 1964

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Red Bed	0	280	Ran 264' of used 8-5/8" surface casing; set and cemented at 272' with 250 sacks of regular cement, 2% gel and 3% calcium chloride. Cement circulated. Plug down at 8:45 A. M. November 20, 1964.
Red Bed & Sand	280	577	
False Anhydrite	577	589	
Anhydrite	589	615	
Red Bed & Shale	615	1245	
Red Bed, Shale & Shells	1245	1595	
Shale & Shells	1595	2500	
Shale & Lime	2500	2665	
Lime	2665	2705	
Lime & Shale	2705	4430	
Lime	4430	4835	
Lime & Shale	4835	5111	

Total Depth 5111'

RECEIVED  
STATE CORPORATION COMMISSION

JUL 14 1965

CONSERVATION DIVISION  
Wichita, Kansas

Ran 160 joints (5114.20') of new 4 1/2" casing; set and cemented at 5109' with 100 sacks of 60-40 posmix with globtex and 10 barrels salt flush ahead of cement. Plug down at 3:45 P. M. December 2, 1964. Pumped plug to 5086'.

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 3rd day of December, 1964.

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965