

OF KANSAS
 CORPORATION COMMISSION
 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,980-00-00

LEASE NAME CARVER

WELL NUMBER 1-31

 Ft. from S Section Line

 Ft. from E Section Line

C W/2 NW SW
 SEC. 31 TWP. 29 RGE. 13 ~~KKKK~~ (W)

COUNTY PRAIT

Date Well Completed

Plugging Commenced 10-23-91

Plugging Completed 10-24-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F G HOLL CO

ADDRESS 6427 EAST KELLOGG WICHITA, KS. 67207

PHONE# (316) 684 8481 OPERATORS LICENSE NO. 5056

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-23-91 (date)

by DAN GOODROW (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation MISSISSIPPIAN Depth to Top Bottom T.D. 4782

PERFS: 4417-20.

Show depth and thickness of all water, oil and gas formations. . .

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	371	8 5/8	371	0
		0	4735	4 1/2	4735	3195 FT.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

10-23-91: RIGGED UP, LOG TECH SET PLUG AT 4354, DUMPED 2 SX CEMENT ON TOP OF PLUG.
LOG TECH SHOT OFF CASING AT 3195 FT, PULLED 76 JTS OF 4 1/2". 10-24-91: TOP HOLE PLUGGED
WITH 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 150 SX. CEMENT. 60-40 POZ,
6% GEL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRAIT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRAIT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F G HOLL

STATE OF KANSAS COUNTY OF PRAIT, ss.

JUDY BERRY PLUGGING CONTRACTOR
 (Employee of ~~XXXXXXXXXXXXXXXXXXXX~~)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Judy Berry

(Address) 40 PWS, Inc.

RECEIVED SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 91
 STATE CORPORATION COMMISSION

NOV 12 1991 My Commission Expires: Feb 16, 1993
Dorothy M. Ferguson Notary Public

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - CARVER #1-31
Located: W/2 NW SW, Section 31-29S-12W, Pratt County, Kansas

OWNER: F. G. Holl Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 6, 1990
COMPLETED: February 17, 1990

TOTAL DEPTH: 4783'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 210 Top Soil - Sand	Ran 7 joints 13 3/8", 48# casing. 322.21' pipe set at 333' K.B. Cemented with 350 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 11:45 PM, 2-6-90, by Howco.
210 - 337 Red Bed	
337 - 4783 Lime and Shale	Ran 118 joints 4 1/2" casing. 4773.32' pipe set at 4782' K.B. Cemented with 100 sacks Lite, 125 sacks F. G. Holl mix. Plug down at 2:00 AM, 2-17-90, by Howco.

Deviation Surveys: 1/2° at 2869'
0° at 4425'
1° at 4783'

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 1991

CONSERVATION DIVISION
WICHITA, KS