

Well # 97


Form CP-1

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Accurate Affidavit  
Must of Before Report to  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD

Location at "NE/CNW/SW" or footage from lines SW SW SE  
County, Sec 29 Twp. 29 Rge. (E) 16 (W)  
Lease Owner: International Petroleum Services Inc  
Lease Name: Goldie Miller Well No. 1  
Office Address: 114 W. Locust El Dorado Kans 67042  
Character of Well (completed as Oil, Gas or Dry Hole) Oil & Gas  
Date well completed \_\_\_\_\_ 10 \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 10 \_\_\_\_\_  
Application for plugging approved 5-9 1974  
Plugging commenced 7-15 1974  
Plugging completed 7-19 1974  
Reason for abandonment of well or producing formation No Production



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production \_\_\_\_\_ 10 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Robertson  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4750 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 13 3/4 | 243    | None       |
|           |         |      |    | 5 1/2  | 4759   | 1925       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged Bottom TO 2660 -  
Dump Sand - From 2660 TO 2500  
5 Bbls of Cement Dumped with Ditch Bailer -  
Cement From 2500 TO 2470  
Ripped at 2000 and 1925  
Wood Bridge at 200  
Back From 200 TO 190  
6 yards of ready mix from 190 TO 180

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1974

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1974

CONSERVATION DIVISION  
Wichita, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor C. D. Mc Coy (SP-7)  
Address Box 187 Medicine Lodge Kansas 67104

STATE OF Kansas COUNTY OF Butler ss.  
R. K. Teichgraber (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. K. Teichgraber

(Address) \_\_\_\_\_

Subscribed and Sworn to before me this 6 day of August 1974

My commission expires Nov 4, 1977  
MAE SAMUELS  
STATE NOTARY PUBLIC  
511 SOUTH GORDY  
EL DORADO, KANSAS 67042  
BUTLER COUNTY, KANSAS

Maer Samuels  
Notary Public.


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- RUPP-FERGUSON OIL CO.  
Farm- Goldie Hillar No. 2

SEC. 29 T. 29 R. 16W  
SW SW SE

Total Depth. 4758'  
Comm. 4-24-56 Comp. 5-13-56  
Shot or Treated.  
Contractor. Rupp-Ferguson Oil.  
Issued. 6-16-56

County Kiowa  
KANSAS



Elevation. 1697' AB

Production. Dry

Figures in quote Pattern of Formations.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 9 - 1974  
CONSERVATION DIVISION  
Wichita, Kansas

|                     |      |
|---------------------|------|
| soil & red bed      | 150  |
| anhydrite           | 243  |
| red bed & shale     | 725  |
| red bed             | 800  |
| lime                | 820  |
| shale & shells      | 1100 |
| salt & shale        | 1290 |
| shale & shells      | 1740 |
| lime & shale        | 1855 |
| lime, shale, sand   | 2020 |
| lime & shale        | 2025 |
| lime                | 2080 |
| lime & shale        | 3220 |
| lime                | 3235 |
| lime, shale streaks | 3335 |
| lime                | 3660 |
| lime & shale        | 3760 |
| lime                | 3820 |
| lime & shale        | 3895 |
| sand & shale        | 3978 |
| sand, shale, lime   | 4034 |
| lime                | 4367 |
| lime & shale        | 4413 |
| lime                | 4448 |
| lime & shale        | 4560 |
| Miss.               | 4648 |
| shale & chert       | 4758 |
| Total Depth         |      |

|                 |      |
|-----------------|------|
| Tops: Scout     |      |
| Heebner         | 3841 |
| Douglas         | 3892 |
| Brown Limestone | 4003 |
| Lansing         | 4023 |
| Mississippi     | 4568 |
| Viola           | 4735 |

*D&A By Rupp Ferguson*  
*Washed down By International Petroleum*  
*9-29-72 RTD 4758 4739'*  
*Cemented w/ 100 Sax*  
*Top cement @ 4357*  
*Feb 1974 Plugged Back to*  
*Cement Bond from 2620 to 2717*  
*Scattered Bond 2300 to 2620*