

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH

Kiowa County, Sec. 29 Twp. 29S Rge. 16(W)

Location as "NE/CNW&SW" or footage from lines C SW $\frac{1}{4}$, SW $\frac{1}{4}$
Lease Owner Graham-Michaelis Corporation
Lease Name Pratt Well No. 1-29
Office Address P. O. Box 247, Wichita, Kansas 67201
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 19, 1974
Application for plugging filed Nov. 22, 1974
Application for plugging approved (verbal) Nov. 19, 1974
Plugging commenced Nov. 19, 1974
Plugging completed Nov. 19, 1974
Reason for abandonment of well or producing formation None - D&A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (verbal)

Name of Conservation Agent who supervised plugging of this well G. Russ Biberstein, Attica, Kansas
Producing formation none Depth to top _____ Bottom _____ Total Depth of Well 4641 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	424'	none

STATE RECEIVED
CORPORATION COMMISSION
NOV 25 1974
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 450'. 40 sax of cement plug from 450' to 300'. Filled with heavy mud to 45'. Had 15 sax of cement. Plug from 45' to surface and 2 sax of cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jack L. Yinger (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Yinger Geologist
P. O. Box 247, Wichita, Kansas 67201
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1974

My commission expires _____

MURIEL F. C. JERAM
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMMISSION EXPIRES
JULY 25, 1976

Muriel F. C. Jeram
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Pratt #1-29
 C-SW-SW Sec 29-29S-16W
 Kiowa County Kansas

Commenced: 11-6-74
 Completed: 11-19-74

OPERATOR: GRAHAM-MICHAELIS CORP.

From	Depth to	Formation	Remarks
0	40	Surface Clay	
40	70	Shale-Rock	
70	426	Redbed-Shale-Gyp	Ran 12 jts of 23# 8 5/8" csg.
426	1217	Redbed-Gyp	set @ 424' Cemented w/
1217	1487	Shale-Lime	200 sks Liteweight 2%CC
1487	1875	Shale	150 Sks Common 3% CC
1875	2018	Salt-Shale-Lime	PD @ 11:15 a.m. 11-7-74
2018	2160	Lime	
2160	2867	Lime-Shale	
2867	2987	Shale-Lime	
2987	3493	Lime-Shale	
3493	3627	Shale-Lime stks	
3627	3736	Shale-Lime	
3736	3839	Lime	
3839	4035	Lime-Shale	
4035	4641	Lime	
	4641 TD		

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 11 1974
 CONSERVATION DIVISION
 Wichita, Kansas
 DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-SW-SW Sec 29-29S-16W, Kiowa County Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 25th day of November, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 MARJORIE HALL-NOTARY PUBLIC

My Commission Expires: November 29th, 1975

