

TATE CORPORATION
TATE CORPORATION COMMISSION
00 Colorado Derby Building
Ichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21172-0000

LEASE NAME Slief

WELL NUMBER 2

1980 Ft. from S Section Line

4470 Ft. from E Section Line

SEC. 11 TWP. 29S RGE. 18 ~~XX~~or(W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 3-27-92

Plugging Completed 3-27-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Fina Oil & Chemical Company

ADDRESS P.O. Box 2990, Midland, TX 79702

PHONE# (915) 688-0600 OPERATORS LICENSE NO. 5692

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 10, 1992 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Crouse LS Depth to Top 2888 Bottom 2898 T.D. 4970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Osage (Miss)	Oil & Gas	4876	4900	8 5/8"	519'	3'
Crouse LS	Water	2888	2916	4 1/2"	4969'	3'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. NA

Address Box 31, Russell, Kansas 67655

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Fina Oil & Chemical Company

STATE OF Texas COUNTY OF Midland, ss.

Ken Fairchild (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Ken Fairchild

(Address) P.O. Box 2990, Midland, Texas 79702

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1992

Dana Toller 8-10-92

My Commission Expires: 2-9-94



**Plugging Report
for the
Slief #2 - API # 15-097-21172
Kiowa County, Kansas**

Rigged up Allied Cementing to casing head. Pump 300# cotton seed hulls, 40 sacks of 60/40 POZ with 8% gel & displace with water. Pump pressure increased to 3200 psi when cotton seed hulls reached perforations at 2888'. Rigged down cement equipment & rigged up Western-Atlas wireline truck. Ran in hole with casing gun and perforated 4½" production casing at 1069' with 4 jet shots. Rigged up cementers & pumped 75 sx 60/40 POZ cement with 8% gel. Shut-in casing pressure was 0 psi. Plumb pump line to surface casing/production casing annulus & pump 160 sacks of 60/40 POZ cement with 8% gel. Final pressure was 50 psi when pumps were shut down. Operations witnessed by Steve Pfeifer of Kansas Corporation Commission on March 37, 1992.

[Faint, illegible text and a circular stamp are visible in the bottom left corner of the page.]