


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Kiowa County. Sec. 11 Twp. 29 Rge. (E) 18 (W)
Location as "NE/CNW%SW%" or footage from lines NE NE SW
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Klug Well No. 1
Office Address 522 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-10-56 19
Application for plugging filed 10-10-56 19
Application for plugging approved 10-10-56 19
Plugging commenced 10-10-56 19
Plugging completed 10-10-56 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 5017 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	340	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 330, hulls, plug, 30 sacks cement & mud to 30'. Plug, hulls, cement to cellar base.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) of Klug of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1956

My commission expires June 4, 1959

RECEIVED
STATE CORPORATION COMMISSION Notary Public.

PLUGGING
FILE SEC. 11 T. 29 R. 18 W
BOOK PAGE 107 LINE 14

OCT 16 1956 10-16-56
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Klug
NE NE SW, Sec. 11-29-18W,
Kiowa County, Kansas

Commenced: 9-24-56
Completed: 10-10-56
Contractor: Rupp-Ferguson Oil Co.

Set 340' of 13 3/8" surface casing w/300 sacks cement.

Figures Indicate Bottom of Formation

75 surface shale & clay
248 same
355 shale
400 shale & shells
420 sand
585 red bed
600 Anhydrite
1180 shale & shells
1205 Anhydrite
1215 shale & shells
1300 salt
1520 salt, shale & shells
2300 shale & shells
2460 lime & shale
2735 lime
3900 shale & lime
4008 lime
4250 lime & shale
4622 lime
4680 lime & shale
4716 lime
4841 lime & shale
5017 Miss.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1956


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Klug well.


L. W. Knox

Subscribed and sworn to before me this 15th day of October, 1956.


Notary Public

My Commission Expires June 4, 1959.

PLUGGING
FILE SEC 11 T 29 R 18W
BOOK PAGE 107 LINE 14