

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,055-0000

LEASE NAME Burchett

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION C SE NW

SEC. 4 TWP. 29 RGE. 18 (X) or (W)

COUNTY Kiowa

Date Well Completed 8-18-84

Plugging Commenced 8-18-84

Plugging Completed 8-18-84

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market - Suite 1110, Wichita, Kansas 67202

PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4969

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud-fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. plugged well with 140 sxs 60/40 poz, 2% gel, 3% cc as follows: 1200'-50 sxs; 570'-50 sxs; 40'-10 sxs; rathole-15 sxs; mousehole-10 sxs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Vincent F. Hiebsch, President, Vincent Oil Corp. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well submitted and filed that the same are true and correct, so help me God.

SEP 13 1984

(Signature) Vincent F. Hiebsch


(Address) 125 N. Market, Suite #1110
Wichita, Ks. 67202

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 23 day of August, 1984

Ruth N. Benjamin
Notary Public

My Commission expires: June 17, 1985



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Burchett #1
 C SE NW Sec. 4-295-18W
 Kiowa County, Kansas
 Commenced; 8-7-84
 Completed: 8-18-84
 API #15-097-21,055
 Operator: Vincent Oil Corporation


Depth		Formation	Remarks
From	To		
0	230	Clay, Sand	Ran 12 joints (504') new, 23#, '8rd, 8 5/8" surface casing. Set at 519' with 300 sxs Class A, 3% cc. Job by Buie, ticket #3126. Cement did circulate. Plug down at 11:50 a.m. on August 8, 1984.
230	720	Gray Shale, Red Bed	
720	1100	Red Bed, Shale	
1100	1225	Red Bed	
1225	1860	Red Bed, Shale	
1860	4910	Lime, Shale	
4910	4928	Mississippi	
4928	4932	Lime	
4932	4942	Lime, Shale	
4942	4948	Mississippi	
4948	4969	Lime, Shale	
			Plugged well with 140 sxs 60/40 poz, 2% gel, 3% cc as follows: 1200'-50 sxs; 570'-50 sxs; 40'-10 sxs; Rathole-15 sxs; mousehole-10 sxs; water well-5 sxs. Job by Buie, ticket #3107. Complete at 11 a.m. 8-18-84. State plugger was Paul Luthi out of the Dodge City, Kansas office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

L. R. Belding
 L. R. BELDING, VICE-PRESIDENT



RECEIVED
 STATE CORPORATION COMMISSION

AUG 24 1984
 MARY L. TJADEN
 NOTARY PUBLIC

My Commission Expires:

3/22/88

CONSERVATION DIVISION
 Wichita, Kansas