

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Kiowa County, Sec. 4 Twp 29s Rge. 18 (E) (W) (W)

Location as "NE/CNW/SW" or footage from lines NW NW

Lease Owner Clinton Oil Company

Lease Name Elsie Burchett Well No. 1-V

Office Address 217 N. Water Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 5 19 73

Application for plugging filed March 5 19 73

Application for plugging approved March 5 19 73

Plugging commenced March 6 19 73

Plugging completed March 6 19 73

Reason for abandonment of well or producing formation No productible zone


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4945 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	459	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned up pits forming heavy mud. Filled hole with heavy mud. Spotted 50 sacks

cement at 350 feet. Filled hole with heavy mud, bridged hole at 40 feet and capped

with 10 sacks cement to base of well cellar. Job complete at 9 AM 3-6-73

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1973 13-110-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address Box 1164 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Ben E. Unruh (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben E. Unruh

Box 1164 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March 19 73

My commission expires 7-8-74

George C. Morris
Notary Public.


WELL LOG

COMPANY **Clinton Oil Company**
FARM **Elsie Burchett** NO. **1-V**
TOTAL DEPTH **4945'**
COMM. **2-21-73** COMP. **3-6-73**
CONTRACTOR **Garvey Drilling Company**

SEC. 4 T29S R. 18W

LOC. NW NW

COUNTY **Kiowa, Kansas**



CASING
8 5/8" @ 459' w/300BX

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

380' Clay & Sand
460' Shale & Red Bed
1186' Red Bed
1212' Anhydrite
2010' Shale & Red Bed
2445' Shale & Lime
2650' Lime & Shale
3605' Shale & Lime
3635' Lime & Shale
4040' Lime
4160' Lime & Shale
4235' Lime
4300' Lime & Shale
4345' Lime
4943' Mississippian Chert
4945' Mississippian
4945' RTD

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1973
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Elsie Burchett #1-V well.

Subscribed and sworn to before me this 7th day of March

My Commission Expires: July 8, 1974

Charlene Marker

James A. [Signature]
NOTARY PUBLIC