


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 28 Twp. 29 Rge. (E) 18 (W)
Location as "NE/CNWxSWx" or footage from lines C NE - SW
Lease Owner Misco Industries, Inc.
Lease Name Koehn Well No. 2
Office Address Misco Bldg. Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 11-8- 1971
Plugging completed _____ 11-10- 1971
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production Unknown 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Miss Chert Depth to top _____ Bottom _____ Total Depth of Well 5034 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 7/8	395	None
				5 1/2	5033	3231

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Push plug to 4500 ft.- rock bridge to 4475 ft. Dump 5 sax cement.
Pull 3231 ft. 5 1/2" pipe - bail hole down to 260 ft.- rock bridge to 240 ft.- dump 4 yds feady mix cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock Pipe Pulling, Inc. Permit # 490
Address 320 N. Park Stafford, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas R. Sproul (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas R Sproul

Misco Bldg., Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 71

My commission expires March 22, 1972
Celeste Kinzie Notary Public.



WELL LOG

COMPANY: GULF OIL CORPORATION

C-NE-SW Sec. 28-29S-18W

FARM: V. H. KOEHN NO. 2

Loc. NE SW

TOTAL DEPTH - 5034'

County - Kiowa

COMM: 4-14-56. COMP: 5-4-56.

CASING

8-5/8" - 394.81' -

5-1/2" - 5033' ✓

Cemented w/125 sacks

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1971
CONSERVATION DIVISION
Wichita, Kansas

ELEVATION

D.F. - 2200

Gr. -

KB - 2703

DRILLER'S LOG

Sand, Red Bed & Clay	0	790
Clay	790	1004
Shale & Shells	1004	2383
Lime & Shale	2383	2495
Lime	2495	2891
Lime & Shale Stks.	2891	2977
Lime	2977	3137
Lime & Shale Stks.	3137	3245
Lime & Shale	3245	4494
Lime	4494	4611
Lime & Shale Stks.	4611	4661
Lime	4661	4804
Lime & Shale	4804	4910
Core No. 1	4910	4939
Core No. 2	4939	4959
Lime	4959	4960
Core No. 3	4960	4998
Lime	4998	5034

Total Depth

5034

Potential - "F" 330.51 BO thru 17/64" choke in 16 hrs.
on state drawdown test.

Indicated capacity - 5059 BO.