

1 040639

3-27

API NUMBER 15- 097-21,172-0000

197P

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

APP. NW SW, SEC. 11, T. 29 S, R. 18 W/EX

1980 feet from S section line

4470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Lease Name Slief Well # 2

Operator: Fina Oil & Chemical Company  
Name & Address: 1601 N.W. Expressway, Ste. 900  
Oklahoma City, OK 73118

County Kiowa

Well Total Depth 4970 161.52 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 519

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Fina License Number 5692

Address P.O. Box 209, Russell, KS 67665

Company to plug at: Hour: 10 a.m. Day: 27 Month: 3 Year: 19 92

Plugging proposal received from Don Tiffin

(company name) Fina (phone) 913-483-2102

were: 4 1/2" at 4969' w/300 sx cement, PBTD 2903', Perfs at 2888-98'

1st plug pump down 4 1/2" casing with 300 lbs. hulls, 40 sx cement, 10 sx gel, displace with water to 1100',

2nd plug perforate 4 1/2" casing and pump 75 sx cement in 4 1/2".

3rd plug pump 160 sx cement down backside.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 27 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 300 lbs. hulls, 40 sx cement, and 10 sx gel. Displaced with 14 bbls. fresh water, squeezed at 3200#.

2nd plug perforated with 4 holes at 1068'. Pumped down 4 1/2" casing with 75 sx cement,

3rd plug pumped down 4 1/2" X 8 5/8" annulus with 160 sx cement.

Maximum pressure 350 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 4-22-92

APR 01 1992

Signed [Signature] (TECHNICIAN)

INV. NO. 34976

JUL 08 1992

CONSERVATION DIVISION Wichita Kansas