

1040781

9-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,296-0000

C NE NE, SEC. 28, T 29 S, R 18 W X E

4690 feet from S section line

730 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Allen Schmidt Well # 1

Operator: Vincent Oil Corporation

County Kiowa

Name & Address 100 N. Main, Ste. 500

Well Total Depth 5015 162.98 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:15 a.m. Day: 15 Month: 9 Year: 1993

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4969' w/150 sx cement, Open hole 4969-5015'

1st plug sand back to 4910' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 15 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 4910' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

SEP 17 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

(did not observe this plugging.)

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 9-23-93

REV. NO. 38771