

To: 1 050630
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,174-0000 *R*

SW SW NE, SEC. 36, T 29 S, R 18 W/X
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: TXO Production Corp.
Name & Address: 200 W. Douglas, Suite 300
Wichita, KS 67202

Lease Name Jenkins "G" Well # 1
County Kiowa 164.13
Well Total Depth 5050 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Freeman Drilling Co. License Number 5106
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7:00 am Day: 31 Month: August Year: 19 85

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2085
Anhydrite 1090

1st plug at the base of the Anhydrite with 50 sx cement
2nd plug 30' out of the base of the surface pipe with 50 sx cement
3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement
5th plug to circulate rat hole with 10 sx cement,
6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:45 am Day: 31 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement, 2nd plug at 450' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate
mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix by Halliburton
(If additional state or federal information necessary, use BACK of this form.)

INVOICED

DATE OCT 03 1985
INV. NO. 10347

SEP 27 1985
9-27-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)