

To: 1041305
STATE CORPORATION COMMISSION 5-13
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 13-097-20899-0000
NE NE 1/4 SEC. 1, T 29 S, R 16 W
4950 feet from S section line
330 feet from E section line
Lease Name Freda Dunbar Well # 3
County Kiowa 155.03
Well Total Depth 4770 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 418'
Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Operator License 18061
Operator: Oil Producers, Inc. of Kansas
Name
Address P.O. Box 8647
Wichita, KS. 67208

Other wells as hereinafter indicated _____
Plugging Contractor D. S. & W. Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS.

Company to plug at: Hour: 10:45 AM Day: 13 Month: 5 Year: 1998
Plugging proposal received from Kent Strube
(company name) D.S. + W. Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" csg. @ 4768' w/150 sx. cmt, P&TD @ 4724', Perfs @ 4690'-4706'
1st plug sand back to 4640' + dump 4 sx cmt. on top of sand through bailer,
2nd plug pumped down 8 5/8" surface pipe w/ 300# hulls, 10 sx gel, 50 sx cmt,
10 sx gel, 100# hulls, 8 5/8" wiper plug, 150 sx cmt.

RECEIVED
STATE CORPORATION COMMISSION
5-19-98
MAY 19 9 1998
Plugging Proposal Received by Kevin Strube
(TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:30 AM Day: 13 Month: 5 Year: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 4625' + dumped 4 sx. cmt. on top of
sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe w/ 300# hulls, 10 sx gel, 50 sx cmt, 10 sx gel,
100# hulls, 8 5/8" wiper plug, 150 sx. cmt.

Max. PSI = 600# S.I.P. = 100#

Remarks: Used 60/40 poz mix 6 gel by Allied. Recovered 2600' of 4 1/2" csg.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-20-98 observe this plugging.

INV. NO. 50592

Signed Stephan J. Pofuda
(TECHNICIAN)