

To: 1 030658
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,578-0002
C S/2 NE NW SEC. 1, T 29 S, R 16 W/E
4290 feet from S section line
3300 feet from E section line
Lease Name Starkey Well # 1-1
County Kiowa 153.73
Well Total Depth 4730 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 406

TECHNICIAN'S PLUGGING REPORT
Operator License # 9869
Operator: Chapman Energy, Inc.
Name & Address 120 S. Market, Suite 320
Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 7 Month: February Year: 19 86

Plugging proposal received from Elmo Morgenstern
(company name) Clarke (phone) 316-886-5665
were: 5 1/2" at 4715' Perfs at 4634-42'; 4607-11'

1st plug sand back to 4550' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:45 pm Day: 7 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4550' and dumped 5 sx cement on top of
sand through dump bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 150 psi FEB 17 1986 2-17-86

Remarks: Recovered 2700' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cons by BT-Tison.
(If additional description is necessary, use BACK of this form.)

INVOICED (copy to client) observe this plugging.

DATE 1-17-86
INV. NO. 12613

Signed Steve Belmont
(TECHNICIAN)