

1030253

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-20,922-0000

C SW NE, SEC. 1, T 29 S, R 16 W/X  
3300 FSL feet from N SE Corner of WXX section line  
1980 FEL feet from W SE Corner of WXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8819

Lease Name Freda Dunbar Well # 5

Operator: Cinco Energy Company

County Kiowa

Name & Address P. O. Box 3723

Well Total Depth 4768 154.96 feet

Victoria, TX 77903-3723

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 445

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:00 am Day: 21 Month: August Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 4765' PBDT 4740' Perfs 4668-88'

1st plug sand back to 4620' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel 1 sack hulls, release 8 5/8"

rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Steve Almont  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:40 am Day: 21 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4765' PTD 4740' Perfs 4668-88'

1st plug sanded back to 4620' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released

8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 550 psi and shut in pressure 350 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
8-24-84  
AUG 24 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 3100' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton.  
(If additional description is necessary, use BACK of this form.)

(old or expert) observe this plugging.

Signed Steve Almont SD  
(TECHNICIAN)

INVOICED

DATE 8-29-84

INV. NO. 3409