

1 060924

JAN 0 8 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8565

Operator: Huey Grey
Name & Address: Rt. 1, Box 47
Greensburg, KS 67054

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:45 a.m. Day: 8 Month: 1 Year: 19 87

Plugging proposal received from Huey Grey

(company name) Huey Grey (phone) 316-723-3123

were: 4 1/2" at 4802' Perfs at 4438-42' Elevation 2323'GL

1st plug sand back to 4790' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 gel, 50 sx cement, 10 gel, 1 sx hulls

and 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx

hulls, and 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Recovered 3150' of 4 1/2" pipe. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-12-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 15875

1-8