

1 060925

JAN 0 8 1987

API NUMBER 15-097-21,144-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SE, SEC. 18, T 29 S, R 18 W XX

990 feet from S section line

1650 feet from E section line

Lease Name Grey Well # 8

County Kiowa 156.00

Well Total Depth 4800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 382

TECHNICIAN'S PLUGGING REPORT

Operator License # 8565

Operator: Huey Grey

Name & Address Rt. 1, Box 47

Greensburg, KS 67054

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 P.M. Day: 8 Month: 1 Year: 1987

Plugging proposal received from Huey Grey

(company name) Huey Grey (phone) 316-723-3123

were: 4 1/2" at 4672' Perfs at 4398-4402'

1st plug sand back to 4348' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

and 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1:15 P.M. Day: 8 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4348' and dump 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Recovered 3130' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
1-12-87
JAN 12 1987
CONSERVATION DIVISION
Wichita, Kansas

observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 1-12-87

INV. NO. 15874 1-8