

1060355

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-21, 022-0000

SW SE SE, SEC. 18, T 29 S, R 18 W/X  
330 feet from ~~N~~ SE Corner of ~~N~~ section line  
990 feet from ~~W~~ SE Corner of ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8565

Lease Name Grey & Grey Well # 4

Operator: Huey P. Grey

County Kiowa

Name & Address Rt. 1, Box 47

Well Total Depth 4850 157.63 feet

Greensburg, KS 67054

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Services License Number 5893

Address P: O: Box 847, Pratt, -KS 67124

Company to plug at: Hour: 9:00 am Day: 3 Month: October Year: 19 84

Plugging proposal received from James Grey

(company name) Huey P. Grey (phone) 316-723-3123

were: 4 1/2" set at 4837' PBD 4606' Perfs from 4379-4718'

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 125 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 am Day: 27 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4837' PBD 4606' Perfs from 4379-4718'

1st plug sanded back to 4330' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel and

125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 05 1984

Maximum pressure 700 psi and shut in pressure 0

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

CONSERVATION DIVISION  
Wichita, Kansas

If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

INVOICED

DATE 10-8-84

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 4132

9-27