

10-27-87

To: 1 050951
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,251-0000
NE NE NE of SEC. 18, T 29 S, R 18 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Operator: Ramco Drilling Services, Inc.
Name & Address: P.O. Box 99
Belpre, Ohio 45714

4680 feet from S section line
600 feet from E section line

Lease Name Donald Koehn Well # 1

County Kiowa 165.75

Well Total Depth 5100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____ (Ran pipe but never produced)

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 27 Month: 10 Year: 19 87

Plugging proposal received from Kendall Sutter

(company name) Ramco Drilling Services, Inc. (phone) 614-423-9591

were: 5 1/2" at 5100' Anhydrite 1280' Elevation 2303' GL

1st plug sand back to 4960' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1280',

3rd plug pump 50 sx cement at 400',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 27 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4960' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 50 sx cement at 1280',

3rd plug pumped 50 sx cement at 400',

4th plug pumped 50 sx cement at 40'.

All plugs spotted through tubing.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3175' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacy (TECHNICIAN)

DATE 11-2-87

INV. NO. 18748

10-27 DEC 03 1987

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1987
10-29-87
CONSERVATION DIVISION
Wichita, Kansas

SAR

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 9-22-87 month day year

API Number 15-097-21,251 yed

OPERATOR: License # 3536 Name RAMCO Drilling Services, Inc. Address P.O. Box 99 City/State/Zip Belpre, Ohio 45714 Contact Person Bob Williamson / David Gocke Phone (614) 423-9591

NE NE NE Sec. 18 Twp. 29 S, Rg. 18 4680 Ft. from South Line of Section 600 Ft. from East Line of Section

CONTRACTOR: License # 5302 Name Red Tiger Drilling Co. City/State Wichita, Kansas Well Drilled For: 172015 Well Class: Storage Type Equipment: X Oil Storage X Mud Rotary

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 600 feet County Kiowa Lease Name Donald Koehn Well # 1 Ground surface elevation 2303 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 170 feet Depth to bottom of usable water 300 feet Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 350 feet Conductor pipe required 5100 Projected Total Depth Mississippiian Formation

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 9-17-87 Signature of Operator or Agent Title Vice-Pres. / Engineering

For KCC Use: Conductor Pipe Required 250 feet; Minimum Surface Pipe Required 250 feet per Alt. This Authorization Expires 3-18-88 Effective 9-23-87 Approved By P.H. 9-18-87

Move in 9-21-87 8 5/8 @ 356' of 8 5/8 W W

Sec. 18 Twp. 29 S, Rg. 18 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, formation, and cement type. Includes entries for 1st, 2nd, 3rd, 4th, and 5th plugs, and rathole/mousehole details.

Table for recording plugging details: PUSHER, TD, SURFACE PIPE @, ANHYDRITE ELEVATION, STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN.

RECEIVED STATE CORPORATION COMMISSION OCT 29 1987 CONSERVATION DIVISION Wichita, Kansas