

1 060035

9-11

21016

API NUMBER 15-097-20,953-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE SE, SEC. 18, T 29 S, R 18 W/E

330 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3344

Lease Name Grey Well # 3

Operator: Magnum Oil & Gas

County Kiowa 159.29

Name & Address Rt. 1, Box 49

Well Total Depth 4900 feet

Greensburg, KS 67054

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 441

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:20 a.m. Day: 11 Month: 9 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4825' w/200 sx cement, PBSD 4825', Perfs at 4368-70'

1st plug sand back to 4318' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:05 a.m. Day: 11 Month: 9 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sand back to 4318' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 20 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2180' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE: 9-17-90

INV. NO. 29340

Signed: [Signature] (TECHNICIAN)

9-13-90