

11-8

To: 1 040348  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,926-0000

S/2: SW SW, SEC. 18, T 29 S, R 18 W/4E

330 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Unruh-Grey Well # 1

Operator: TXO Production Corporation  
Name &

County Kiowa 167.44

Address 1660 Lincoln St., Suite 1800  
Denver, CO 80264

Well Total Depth 5152 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 410

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 8 Month: 11 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 816-886-5665

were: 4 1/2" at 5123' PBD 4440' Perfs 4422-5074' (7 sets) Cement retainer at 4440'

1st plug sand back to 4370' and dump 4 sx cement on top of sand bridge with bailer.

2nd plug pump down 8 5/8" with 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 8 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

7 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx

Maximum pressure 600 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2700' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 11-17-89

Signed Stephen J. Pfeifer (TECHNICIAN) R9W2

INV. NO. 26496