

11-2/

To: 1 061165
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,083-0000
SE SE SW, SEC. 18, T 29 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corporation
Name & Address: 1660 Lincoln Street, Suite 1800
Denver, CO 80264

650 feet from S section line

2970 feet from E section line

Lease Name Unruh-Grey Well # 4

County Kiowa 159.25

Well Total Depth 4900 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 412

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:45 p.m. Day: _____ Month: 11 Year: 19 88

Plugging proposal received from Elmo Morganstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4899' 4886' Float, 4536' CIBP

1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
11-23-88
NOV 23 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 21 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of

sand through bailer.

2nd plug pumped 4 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc by B.J. Titan. Recovered 3000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE DEC 1 1988

Signed Paul A. Luthie (TECHNICIAN)

INV. NO. 22220