

1 051336

8-6

15-0971-21010-0003

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-D-23,771

SE NE SW, SEC. 18, T 29 S, R 18 W/E
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Unruh-Grey Well # 3

Operator: TXO Production Corporation

County Kiowa 159.25

Name & Address 1660 Lincoln St., #1800

Well Total Depth 4900 feet

Denver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 6 Month: 8 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4895' w/350 sx cement, PBT 4800', Perfs at 3898-3906, 3916-32, 3990-4004, 4768-90, 4812-16'

1st plug set CIBP at 4050' and 3850' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 6 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4050' and 3850' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 7 sx gel, 1 sx hulls and 125 sx cement.

STATE CORPORATION COMMISSION

AUG - 9 1990

8-9-90

CONSERVATION DIVISION

Wichita, Kansas

Witnessed by Steve Middleton.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2900' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(if desired, witness observe this plugging.)

INVOICED

Signed Richard W. Lucy (TECHNICIAN)

DATE: 8-23-90

INV. NO. 29028