

1090038

1-9

153

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,092-0000
SW NE NE, SEC. 16, T 29 S, R 16 W/X

TECHNICIAN'S PLUGGING REPORT

4290 feet from S section line
1990 feet from E section line

Operator License # 4174

Lease Name McClure Well # 1

Operator: Western Oil Corporation

County Kiowa 154.41

Name & Address P.O. Box 15277

Well Total Depth 4751 feet

Lakewood, CO 80215

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 520

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12 p.m. Day: 9 Month: 1 Year: 19 90

Plugging proposal received from Bob Sargent

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 4751' Perfs at 4730-36' TOC 3780' Elevation 2028' GL

1st plug pump 1 sx hulls and 20 sx cement at perforations,

2nd plug pump 50 sx cement at 1050'

3rd plug pump 40 sx cement at 550'

4th plug pump 10 sx cement at 40'

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 4 p.m. Day: 9 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 4100',

2nd plug pumped 50 sx cement at 1050',

3rd plug pumped 40 sx cement at 550',

4th plug pumped 10 sx cement at 40'.

RECEIVED STATE CORPORATION COMMISSION

JAN 16 1990 1-16-90

Remarks: Used common cement by Sargent's. Recovered 2651' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed Michael R. Wilson (TECHNICIAN)

DATE 1-30-90

INV. NO. 27242

MAR. 1, 1990 FEB 28 1990