

1031318 4-3

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-20,492-0001

E/2 NE, SEC. 9, T 29 S, R 17 W/E
3960 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3067
Operator: Molitor Oil, Inc.
Name:
Address: RR 1, Box 74
Spivey, KS 67142

Lease Name Conklin Well # 1-9
County Kiowa
Well Total Depth 4848 157.56 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number 31201
Address Greensburg, KS

Company to plug at: Hour: 5:45 p.m. Day: 3 Month: 4 Year: 19 95

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

were: 5 1/2" at 4808' w/135 sx cement, PBSD 4808'; Perfs at 4749-4784'
1st plug sand back to 4700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:30 p.m. Day: 3 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4625' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
4-6-95

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2706' of 5 1/2" casing. APR - 6 1995

(If additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED
DATE 4-13-95
42567

Signed Steve Durrant
(TECHNICIAN)