

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21203-00-00
Spot: CW2W2SW Sec/Twnshp/Rge: 12-29S-18W
1320 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: UNRUH C Well Number: 1
County: KIOWA Total Vertical Depth: 4971 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size feet: 3/61.56
Surface Casing: Size 8.625 feet: 519 WITH 150 SX CMT
Production: Size 4.5 feet: 4969 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/21/2002 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3510' & 4 SX CMT. 1ST PLUG AT 1150' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/21/2002 10:40 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 3719'. PERFS AT 3561-64'. SAND TO 3510' WITH 4 SX CMT ON TOP. LOAD HOLE. 1ST PLUG PULL TO 1165' & SPOT 50 SX CMT - 10 SX GEL. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

RECEIVED

MAY 24 2002


KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2532' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

INVOICED

MAY 22 2002

DATE 5-28-02

INV. NO. 2002061846

