

No: 1 050660
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,192-000
E/2 NW/4 SEC. 13, T 29 S, R 18 W/4
4620 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5238
Operator: Petroleum, Inc.
Name & Address 300 W. Douglas
Suite 800
Wichita, KS 67202

Lease Name Gobin "C" Well # 1
County Kiowa 162.34
Well Total Depth 4995 (Miss) feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 637 ✓
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____
Plugging Contractor Mustang Drilling & Exploration License Number 5652
Address Box 1609, Great Bend, KS 67530
Company to plug at: Hour: 11:00pm Day: 31 Month: October Year: 1985

Plugging proposal received from Gib Overbey
(company name) Mustang Drilling & Exploration (phone) 316-792-7323
were: ~~to~~ To keep hole full of good drilling mud + spot
plugs through drill pipe. 1st plug at the base of
the Anhydrite with 50sx of cement. 2nd plug 30'
below the base of the surface pipe with 40sx of cement.
3rd plug @ 40' with 10 sx of cement. Circulate the
Rathole with 10sx Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 1:00am Day: 1 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of good drilling mud + spotted
plugs through drill pipe 1st plug 1090' w/50sx
of cement. 2nd plug @ 660' w/50sx of cement.
3rd plug @ 40' with a solid bridge plug + 10sx
of cement. Circulated Rathole w/15sx
Anhydrite @ ~~1060'~~

Remarks: BJ Titan pumped 60/40 poz mix 2% gel 3% cc cement
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 11/88
INV. NO. 11188

RECEIVED
OCT 25 1985
STATE CORPORATION COMMISSION
NOV 4 1985
11-14-85
CONSERVATION DIVISION

Signed Richard W. Lacey
(TECHNICIAN)