

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20511-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 24-29S-39W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: V R RAY Well Number: 1  
County: STANTON Total Vertical Depth: 5800 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 WEST OKLAHOMA AVENUE  
ULYSSES, KS 67880

Production Casing Size: 5.5 feet: 5800 WITH 725 SX CMT  
Surface Casing Size: 8.625 feet: 1805 WITH 900 SX CMT

#18850

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/06/2003 12:00 PM  
Plug Co. License No.: 99979 Plug Co. Name: OILWELL CEMENTERS, INC.  
Proposal Rcvd. from: LARRY SMITH Company: OILWELL CEMENTERS, INC. Phone: (918) 223-6731

Proposed Plugging Method: FILL 5 1/2" WITH CMT. TIE ON BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/06/2003 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5714'. PERFS AT 5654-71'. PUMP 50# FLOCELE ON BOTTOM. FOLLOW WITH CMT. FL AT 3488'. PUMP 465 SX CMT FROM PERFS TO GROUND LEVEL. PRESSURE TO 500 PSIG & SHUT IN. RIG UP TO BACKISDE & PUMP 15 SX CMT. PRESSURE TO 400 PSIG & SHUT IN.

RECEIVED  
JUL 16 2003  
KCC WICHITA

Remarks: USED CLASS A CMT WITH 6% GEL BY OILWELL CEMENTERS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED  
JUL - 2 2003  
KCC Dodge City

Signed

Jim Holland  
(TECHNICIAN)

INVOICED

DATE 7-16-03

INV. NO. 2004060069

Form DR-1/3