

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 23 1976  
1-23-76  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
Wichita, Kansas  
New Address  
245 North Water  
Wichita, Kansas 67202

Operator's Full Name A Scott Ritchie

Complete Address 412 Union Center Bldg Wichita, KS

Lease Name Conrardy Well No. 1

Location NW/SW/SE Sec. 11 Twp. 29s Rge. 9 (E) (W) W

County Kingman Total Depth 2502

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 11:00 AM Day 21 Month 1 Year 1976

The above well was plugged as follows:

222 ft 8 5/8 surface cement circulated. 2499 ft 4 1/2 long string  
cemented with 100 sacks. Top perf. 2403 ft. Push plug to 2400ft ,  
4 sacks cement with bailer. Pulled 1965 ft 4 1/2. Set 10 ft rock  
bridge at 220 ft. Fill hole with 3 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 1-23-76  
INV. NO. 2627-W