

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION SW-SW-SE
SEC 29 TWP 29 RGE 16W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Miller

Operator Rudolph Ferguson oil co Address 625 Park Bldg
Wichita Kansas

Field _____ County Kiowa

Total Depth 475-8 Feet.

Plugging Contractor Co Toole Candy Offshore I.P.

Plugging Contractor's License No. Ds

Address Wichita Kansas

(Describe Briefly the manner in which the well was plugged)

13 3/8" 243' L.W.C. hole filled with Heavy
Rotary Mud to 240' set Plug run 25' of cement
Mud to 20' set plug 44' of cement to face
of casing.

M. C. Rivers
District Conservation Agent

Date 5-13-56

RECEIVED
CONSERVATION COMMISSION
MAY 14 1956 5-14-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 29 R 16W
BOOK PAGE 60 LINE 41

CONTRACTOR'S WELL LOG

Rupp-Ferguson Oil Co. Goldie Millar #1
SW SW SE, Sec. 29-29-16W, Kiowa County, Kans.

Contractor: Rupp-Ferguson Oil Co.

Commenced: 4-24-56

Set 243' of 13 3/8" surface csg. w/225 sax.

Completed: 5-13-56 D & A

Figures Indicate Bottom of Formation

150 soil & red bed
 243 Anhydrite
 725 red bed & shale
 800 red bed
 820 lime
 1100 shale & shells
 1290 salt & shale
 1740 shale & shells
 1855 lime & shale
 2020 lime, shale, sand
 2025 lime & shale
 2080 lime
 3220 lime & shale
 3285 lime
 3385 lime, shale streaks
 3660 lime
 3760 lime & shale
 3820 lime
 3895 lime & shale
 3978 sand & shale
 4034 sand, shale, lime
 4367 lime
 4413 lime & shale
 4448 lime
 4568 lime & shale
 4648 Miss.
 4758 shale & chert
 T.D.

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Millar well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 17th day of May, 1956.

RECEIVED
STATE CORPORATION COMMISSION
Selen Horine
Notary Public

MAY 17 1956

My Commission Expires June 4, 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC. 29	T. 29	R. 16W
BOOK	PAGE 60	LINE	41